BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule-B"

Name of Work :- Operation and Maintenance of park light fittings in Ward No.0.2,03 & 04 Package Y-15 of Yelahanka Zone for the Period (10 Months).

Job Code : **P-Code: P0300**

Estimat Amount: 7.25 Lakhs **TS No:**

Sl. No	Description Of Work	Unit	Qty	Quoted Rates	In words
1	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Igniters, Capacitors, Switches , wires, Holders, Starters and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day,Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **125 watt HPMV park lighting systems.**	Each	250	320.00	Three Hundred Twenty Rupees
2	Operation and Maintenance of LED street lighting system including replacement of damaged/failed /fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **24 to 45 watt LED street lighting System.**	Each	632	390.00	Three Hundred Ninety Rupees
3	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **150 to 180 watt LED street lightingsystems.**	Each	30	650.00	Six Hundred Fifty Rupees
4	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **200 to 300 watt LED street lightingsystems.**	Each	25	600.00	Six Hundred Rupees

I am prepared to take up the above work at rates quoted in the Schedule 'B'

For Vaishnavi Enterprises

Proprietor

Contractor

EXECUTIVE ENGINEER
(ELEC)
BBMP, Yelahanka Zone